

**YANAM MUNICIPALITY  
YANAM**

**Schedule "A" 1/2**

**Name of work: Construction of R.C.C. Mandapam in front of Community hall at Vamsi Krishna Colony at Mettakuru, Yanam**

Sl. No.	Code No. & Description of Item.	Qty.	Rate in		Per	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	2.6.1 Earth work in excavation over areas (exceeding 30cm in depth, 1.5m in width as well as 10sqm on plan) including disposal of excavated earth lead upto 50m and lift upto 1.5m; disposed earth to be levelled and neatly dressed - all kinds of soil.	70.00 Cum			1 Cum (One Cubic Metre)	
2	2.28 Supplying and filling in plinth with river sand under floors including, watering, ramming consolidating and dressing complete.	19.00 Cum			1 Cum (One Cubic Metre)	
3	4.5.10 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40mm nominal size).	9.00 Cum			1 Cum (One Cubic Metre)	
4	5.1.2 Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level - 1:1.5:3 (1 cement : 1.5 sand : 3 graded stone aggregate 20mm nominal size).	29.00 Cum			1 Cum (One Cubic Metre)	
5	5.2.2 Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering, finishing and reinforcement - 1:1.5:3 (1 cement : 1.5 sand : 3 graded stone aggregate 20mm nominal size).	7.50 Cum			1 Cum (One Cubic Metre)	

1	2	3	4	5	6	7
6	5.3.1 Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15 degree, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral staircases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size).	58.00 Cum			1 Cum (One Cubic Metre)	
7	5.13.1 Reinforced cement concrete work in vertical and horizontal fins individually or forming box louvers, facias and eaves boards upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 sand : 3 graded stone aggregate 20 mm nominal size).	3.00 Cum			1 Cum (One Cubic Metre)	
8	5.14.1 Centring and shuttering including strutting, propping etc. and removal of form for - foundations, footings, bases of columns etc. for mass concrete.	126.00 Sqm			1 Sqm (One Square Metre)	
9	5.14.6 Centring and shuttering including strutting, propping etc. and removal of form for - columns, pillars, piers, abutments, posts and struts.	103.00 Sqm			1 Sqm (One Square Metre)	
10	5.14.5 Centring and shuttering including strutting, propping etc. and removal of form for - lintels, beams, plinth beams,girders, bressummers and cantilevers.	135.00 Sqm			1 Sqm (One Square Metre)	
11	5.14.3 Centring and shuttering including strutting, propping etc. and removal of form for - suspended floor, roofs, landings, balconies and access platform.	357.00 Sqm			1 Sqm (One Square Metre)	
12	5.29.3B Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete - Thermo Mechanical Treated Bars -(TISCON / VIZAG / IISCO / SAIL).	10745.00 kg.			1 Kg. (One Kilogram)	